CONTRACT PLANS COMPONENTS ROADWAY PLANS

SHEET DESCRIPTION

KEY SHEET

INDEX OF ROADWAY PLANS

SHEET NO.

SQ 1 - SQ 3


9-11 12


STATE OF FLORIDA DEPARTMENT OF TRANSPORTATION

CONTRACT PLANS

FINANCIAL PROJECT ID 431734-1-72-09 ORANGE COUNTY (75050000)

STATE ROAD NO. 50





BARRY J. SWITZER, P.E. P.E. NO.: 43422 HNTB CORPORATION 610 CRESCENT EXECUTIVE CT SUITE 400 LAKE MARY, FL 32746 (407) 805-0355 CONTRACT No.: C-9L51 VENDOR No.: VF431623092001 CERTIFICATE OF AUTHORIZATION No.: 6500

FDOT PROJECT MANAGER:

RAUL ARTUZ

PROJECT LOCATION

NEW PORT RICHES

ST PETERSBURG

TAMPA

SARASOT A BRADENT

CONSTRUCTION CONTRACT NO.	FISCAL YEAR	SHEET NO.
E5U46	18	1


CKSONVILLE

DAYTONA BEACH

GOVERNING STANDARD SPECIFICATIONS:

Florida Department of Transportation, July 2017 Standard Specifications for Road and Bridge Construction at the following website: http://www.fdot.gov/programmanagement/Implemented/SpecBooks/

TO ORLANDO



THIS DOCUMENT HAS BEEN DIGITALLY SIGNED AND SEALED BY:


PRINTED COPIES OF THIS DOCUMENT ARE NOT CONSIDERED SIGNED AND SEALED. THE SIGNATURE MUST BE VERIFIED ON THE ELECTRONIC DOCUMENTS.

BARRY J. SWITZER, P.E.
P.E. LICENSE NUMBER 43422
HNTB CORPORATION
610 CRESCENT EXECUTIVE CT, SUITE 400
LAKE MARY, FL 32746
CERTIFICATE OF AUTHORIZATION 6500

THE ABOVE NAMED PROFESSIONAL ENGINEER SHALL BE RESPONSIBLE FOR THE FOLLOWING SHEETS IN ACCORDANCE WITH RULE 61G15-23.004, F.A.C.

ROADWAY PLANS

SHEET NO.	SHEET DESCRIPTION
1	KEY SHEET
2	SIGNATURE SHEET
3	SUMMARY OF PAY ITEMS
SQ 1 - SQ 3	SUMMARY OF QUANTITIES
6	PLAN SHEET
7	DRAINAGE STRUCTURES
8	CROSS SECTIONS
9-11	STORMWATER POLLUTION PREVENTION PLAN
12	UTILITY ADJUSTMENTS



THIS DOCUMENT HAS BEEN DIGITALLY SIGNED AND SEALED BY:

PRINTED COPIES OF THIS DOCUMENT ARE NOT CONSIDERED SIGNED AND SEALED. THE SIGNATURE MUST BE VERIFIED ON THE ELECTRONIC DOCUMENTS.

MATTHEW S. ROSS, P.E.
P.E. LICENSE NUMBER 56977
HNTB CORPORATION
610 CRESCENT EXECUTIVE CT, SUITE 400
LAKE MARY, FL 32746
CERTIFICATE OF AUTHORIZATION 6500

THE ABOVE NAMED PROFESSIONAL ENGINEER SHALL BE RESPONSIBLE FOR THE FOLLOWING SHEETS IN ACCORDANCE WITH RULE 61G15-23.004, F.A.C.

ROADWAY PLANS ROADWAY PLANS

SHEET NO.	SHEET DESCRIPTION
2	SIGNATURE SHEET
4	TYPICAL SECTION
5	PROJECT NOTES

REVISIONS												
DATE	DESCRIPTION	DATE	DESCRIPTION									

HNTB CORPORATION
MATTHEW S. ROSS, P.E.
FL REGISTRATION NO. 56977
610 CRESCENT EXECUTIVE CT SUITE 400
LAKE MARY, FL 32746
(407) 805-0355
CERT. 0F AUTH. NO. 6500

STATE OF FLORIDA
DEPARTMENT OF TRANSPORTATION

ROAD NO. COUNTY FINANCIAL PROJECT ID

SR 50 ORANGE 431734-1-72-09


SIGNATURE SHEET

SHEET NO.

	REVI	SIONS		HNTB CORPORATION	STATE OF FLORIDA				
DATE	DESCRIPTION	DATE	DESCRIPTION	BARRY J. SWITZER, P.E. FL REGISTRATION NO. 43422 610 CRESCENT EXECUTIVE CT SUITE 400 LAKE MARY, FL 32746 (407) 805-0355 CERT. OF AUTH. NO. 6500	DEPARTMENT OF TRANSPORTATION				
					ROAD NO.	COUNTY	FINANCIAL PROJECT ID		
					SR 50	ORANGE	431734-1-72-09		

SUMMARY OF PAY ITEMS

SHEET NO.



	SUMMARY OF LUMP SUM ITEMS											
PAY ITEM	PAY ITEM DESCRIPTION	QUAN	TITY	DESIGN	CONSTRUCTION REMARKS							
NO.	TAI TIEM DESCRITTION	Р	F	NOTES								
101 1	MOBILIZATION	1										
102 1	MAINTENANCE OF TRAFFIC	1										
110 1 1	CLEARING AND GRUBBING	1										

	SUMMARY OF EROSION AND SEDIMENT CONTROL DEVICES											
	SUMIN	TART U	r ERUS	SION A	ND SEL	JIMENI 	CONT	RUL DEVICES				
LOCATION	SIDE		MENT RIER	TURB	TING IDITY RIER	PROTE	LET CTION TEM	DESIGN	CONSTRUCT I ON			
	SIDE	0104	10 3	010	4 11	0104	4 18	NOTES	REMARKS			
STA. TO STA.		LF		LF		EA						
		Р	F	Р	F	Р	F					
201+85.27 TO 202+28.14	LT	<i>52</i>										
202+06 . 35	LT					1						
202+24 . 16	RT					1						
202+97.00 TO 203+23.00	RT			30								
SU	SUB-TOTAL: 52			30		2			·			
	TOTAL:	5 <i>2</i>		30		2						

	REVI	SIONS		HNTB CORPORATION	STATE OF FLORIDA			
DATE	DESCRIPTION	DATE	DESCRIPTION	BARRY J. SWITZER, P.E.	DEPARTMENT OF TRANSPORTATION			
				FL REGISTRATION NO. 43422				
				610 CRESCENT EXECUTIVE CT SUITE 400 LAKE MARY, FL 32746	ROAD NO.	COUNTY	FINANCIAL PROJECT	
				(407) 805-0355 CERT. OF AUTH. NO. 6500	SR 50	ORANGE	431734-1-72-09	

SUMMARY OF QUANTITIES

SHEET NO.

SQ-1

	SUMMARY OF REMOVAL ITEMS											
PAY ITEM NO.	PAY ITEM DESCRIPTION	LOCATION	SIDE	DE UNITS	QUANTITY		TOTAL		DESIGN NOTES	CONSTRUCTION REMARKS		
		STA. TO STA.			Р	F	Р	F				
700 1 50	SINGLE POST SIGN, RELOCATE	201+96.84 TO 202+16.13	LT	AS	2		2					

		SUMMARY OF	PAVEN	1ENT						
PAY ITEM	PAY ITEM DESCRIPTION -	LOCATION	SIDE	UNIT	QUANTITY		TOTAL		DESIGN NOTES	CONSTRUCTION REMARKS
NO.		STA.								
		STA.			P	F	Р	F		
160 4	TYPE B STABILIZATION	201+91.51 TO 202+23.00	LT/RT	SY	77		77			
285 701	OPTIONAL BASE, BASE GROUP 01	201+91.51 TO 202+23.00	LT/RT	5Y	66		66			
337 7 83	ASPH CONC FC, TRAFFIC C, FC-12.5, PG76-22	201+91.51 TO 202+23.00	LT/RT	TN	5.4		5.4			

	SUMMARY OF CURB & GUTTER AND/OR TRAFFIC SEPARATORS													
PAY ITEM	M PAY ITEM DESCRIPTION	LOCATION		SIDE UNI	LINIT	QUANTITY					TOTAL		<i>DESIGN</i>	CONSTRUCTION
NO .		STA. TO STA.	UNII		GROSS	ROSS DEDUCTIONS NET LENGTH		LENGTH			NOTES	REMARKS		
		SIA.	IU SIA.			LENGTH	TYPE	LENGTH	Р	F	Р	F		
520 - 1 - 10	CONCRETE CURB & GUTTER, TYPE F	201+91.51	TO 201+98.41	LT	LF	6.9			7		7			
		202+12.59	TO 202+23.00	LT	LF	10.4	CI Ty4	1	10		10			
520 - 3	CONCRETE VALLEY GUTTER	201+95.00	TO 202+12.59	LT	LF	17.6	CI Ty4	11	7		7			

	HNTB CORPORATION			
DATE	DESCRIPTION	BARRY J. SWITZER, P.E.		
			FL REGISTRATION NO. 43422 610 CRESCENT EXECUTIVE CT S LAKE MARY, FL 32746 (407) 805-0355 CERT. OF AUTH. NO. 6500	

SUITE 400

STATE OF FLORIDA
DEPARTMENT OF TRANSPORTATION ROAD NO. COUNTY FINANCIAL PROJECT ID SR 50 ORANGE 431734-1-72-09

SUMMARY OF QUANTITIES

SHEET NO.

SQ-2

425-1-442 INCLUDES COST OF PRE-FABRICATED UNIT (TREATMENT DEVICE), STRUCTURE BOTTOM, INLET TOP, DELIVERY AND INSTALLATION.
INSTALLATION INCLUDES GROUTING THE INFLOW AND OUTFLOW PIPES AND SETTING THE INLET TOP.

			SU	JMMARY OF PERFORMANCE TURF			
LOCATION	SIDE	PERFORMANCE TURF (SOD) 0570 1 2		DESIGN NOTES	CONSTRUCT I ON REMARKS		
STA. TO STA.		P	SY F	NOTES	NEMANNS		
201+91.51 TO 202+23.00	LT	61		St. Augustine / Match in kind			
SU	61						
TOTAL:		61					

Γ		REVI	SIONS		HNTB CORPORATION BARRY J. SWITZER, P.E. FL REGISTRATION NO. 43422 610 CRESCENT EXECUTIVE CT SUITE 400	STATE OF FLORIDA DEPARTMENT OF TRANSPORTATION		
F	DATE	DESCRIPTION	DATE	DESCRIPTION				
						ROAD NO.	COUNTY	FINANCIAL PROJECT ID
					LAKE MARY, FL 32746 (407) 805-0355 CFRT OF AUTH NO 6500	SR 50 ORANGE	ORANGE	431734-1-72-09

SUMMARY OF QUANTITIES

SHEET NO.

SQ-3

8/24/2017 5:00:38 PM W:\ Johc\61704_FD0T_DW_Drainana(Maintenance)\TW0'c\TW0_2_Spring_Lake_Orlando\47017677705\coadway\SUM

ROADWAY NOTES

- THE BENCHMARK DATUM USED FOR THE PLANS IS THE NORTH AMERICAN VERTICAL DATUM OF 1988 (NAVD 88).
- THE LOCATION(S) OF THE UTILITIES SHOWN IN THE PLANS (INCLUDING THOSE DESINGATED Vv, Vh, AND Vvh) ARE BASED ON LIMITED INVESTIGATION TECHNIQUES AND SHOULD BE CONSIDERED APPROXIMATE ONLY. THE VERIFIED LOCATIONS/ELEVATIONS APPLY ONLY AT POINTS SHOWN. INTERPOLATIONS BETWEEN THESE POINTS HAVE NOT BE VERIFIED.
- UTILITY CONTACTS:

UTILITY AGENCY OWNER TELEPHONE NUMBER

CHARTER COMMUNICATIONS
CITY OF ORLANDO
ORLANDO UTILITIES COMMISSION (OUC) 532-8509 971-5648 (407)434-2303 TECO PEOPLES GAS

- PROVIDE A MINIMUM 2-WEEK NOTICE TO OUC WATER FOR SCHEDULING AND MOBILIZATION. CONTACT LUIS FEBRES 407-434-2533 LFEBRES@OUC.COM
- A "SPECIAL EVENT" IS DEFINED AS A FESTIVAL, FAIR, RUN, RACE, MOTORCADE, PARADE, CIVIC ACTIVITY, CULTURAL ACTIVITY, CHARITY OR FUND DRIVE, SPORTING EVENT, OR SIMILAR ACTIVITY THAT COULD BE NEGATIVELY IMPACTED AS A RESULT OF THE WORK. SPECIAL EVENTS INCLUDE, BUT ARE NOT LIMITED TO, MAGIC BASKETBALL GAMES, AND EVENTS AT THE CAMPING WORLD STADIUM, AMWAY CENTER AND THE DR. PHILLIPS CENTER FOR THE PERFORMING ARTS.
- EXISTING TOPOGRAPHICAL FEATURES ARE BASED ON LIMITED SURVEY DATA AND INFORMATION OBTAINED FROM EXISTING AS-BUILT PLANS. APPARENT RIGHTS OF WAY, EASEMENTS AND PARCEL LINES SHOWN IN THE PLANS ARE APPROXIMATE AND HAVE NOT BEEN SURVEYED OR VERIFIED.

DRAINAGE NOTES

- EXISTING DRAINAGE STRUCTURES TO REMAIN UNLESS OTHERWISE NOTED.
- AN OUTFALL EASEMENT EXISTS PER THE "OUTFALL DITCH EASEMENT DEED" AS ESTABLISHED IN DEED BOOK 753 PAGE 190, DATED SEPT. 17, 1947, DEED BOOK 795 PAGE 84, DATED SEPT. 18, 1947, AND PLAT OF SURVEY FOR LOTS 2 AND 3, BLOCK 3, COUNTRY CLUB ESTATES REPLAT DATED SEPT. 12, 1947 (RECORDED IN PLAT BOOK "Q" PAGE 70, PUBLIC RECORDS OF ORANGE COUNTY, FL). ACCESSIBLITY HAS NOT BEEN VERIFIED. ALTERNATE WATER ACCESS TO SPRING LAKE VIA FDOT RIGHT OF WAY ON SR 500 (US 441).

TEMPORARY TRAFFIC CONTROL NOTES

1. MAINTAIN EXISTING POSTED SPEED LIMITS AT ALL TIMES:

RIO GRANDE AVENUE - 25 MPH SPRING LAKE DRIVE - 25 MPH

- LANE CLOSURES ARE RESTRICTED TO ACTIVE WORK PERIODS.
- CONSTRUCTION ACTIVITIES ARE LIMITED TO THE DAYTIME HOURS OF 8:00 AM TO 5:00 PM.

TEMPORARY TRAFFIC CONTROL PHASE NOTES

PHASE I: THE INTENT OF THIS PHASE IS TO EXCAVATE THE ROADWAY, EXPOSE THE EXISTING PIPE, CONSTRUCT THE DRAINAGE STRUCTURES AND RESTORE THE ROADWAY AND RIGHT OF WAY.


- UTILIZE INDEX 602 TO INSTALL THE REQUIRED EROSION CONTROL MEASURES.
- INSTALL THE ADVANCED WARNING SIGNS AND TRAFFIC CONTROL DEVICES PER INDEX 605.
- PROVIDE FLAGGERS PER INDEX 600 TO REGULATE TRAFFIC THROUGH THE WORK ZONE UNTIL THE
- INSTALL TEMPORARY DETOUR PER THE TEMPORARY TRAFFIC CONTROL DETOUR DETAIL. CLOSURE IS LIMITED TO FIVE CONSECUTIVE DAYS MAXIMUM.
- CONSTRUCT THE PROPOSED DRAINAGE STRUCTURE AND RESTORE THE WORK AREA.
- THIS COMPLETES CONSTRUCTION.

DETAIL LEGEND:

WORK ZONE SIGN

TYPE III BARRICADE

₩ WORK ZONE



TEMPORARY TRAFFIC CONTROL DETOUR DETAIL


REVISIONS HNTB CORPORATION DATE DATE DESCRIPTION MATTHEW S. ROSS, P.E. FL REGISTRATION NO. 56977 LAKE MARY, FL 32746 (407) 805-0355 CERT. OF AUTH. NO. 6500


610 CRESCENT EXECUTIVE CT SUITE 400


STATE OF FLORIDA DEPARTMENT OF TRANSPORTATION ROAD NO. COUNTY FINANCIAL PROJECT ID SR 50 ORANGE 431734-1-72-09

PROJECT NOTES

SHEET NO.







THE FOLLOWING NARRATIVE OF THE STORMWATER POLLUTION PREVENTION PLAN CONTAINS REFERENCES TO THE STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION, THE DESIGN STANDARDS, AND OTHER SHEETS OF THESE CONSTRUCTION PLANS. THE FIRST SHEET OF THE CONSTRUCTION PLANS (CALLED THE KEY SHEET) CONTAINS AN INDEX TO THE OTHER SHEETS. THE COMPLETE STORMWATER POLLUTION PREVENTION PLAN INCLUDES SEVERAL ITEMS: THIS NARRATIVE DESCRIPTION, THE DOCUMENTS REFERENCED IN THIS NARRATIVE, THE CONTRACTOR'S APPROVED EROSION CONTROL PLAN REQUIRED BY SPECIFICATION SECTION 104, AND REPORTS OF INSPECTIONS MADE DURING CONSTRUCTION.

I. SITE DESCRIPTION:

(1) NATURE OF CONSTRUCTION ACTIVITY:

THE FLORIDA DEPARTMENT OF TRANSPORTATION (FDOT) PROPOSES THE INCORPORATION OF A STORM WATER TREATMENT DEVICE CURB INLET STRUCTURE, ONE ADDITIONAL MANHOLE STRUCTURE AND UPGRADING A PIPE RUN UPSTREAM OF AN EXISTING BAFFLE STRUCTURE.
THIS PROJECT IS LOCATED IN ORANGE COUNTY WITHIN THE CITY OF ORLANDO; THE SYSTEM RUNS ALONG SR 50 (W. COLONIAL DR.) AND N RIO GRANDE AVE. AND DISCHARGES INTO THE SOUTH WEST CORNER OF SPRING LAKE. THE PROPOSED IMPROVEMENTS ARE LOCATED AT THE INTERSECTION OF SPRING LAKE DR. AND N RIO GRANDE AVE.

- (2) SEQUENCE OF MAJOR SOIL DISTURBING ACTIVITIES:
 - (a) THE CONTRACTOR SHALL BE REQUIRED TO PREPARE A SITE SPECIFIC EROSION AND SEDIMENT CONTROL PLAN ALONG WITH A DETAILED CONSTRUCTION SCHEDULE TO INDICATE DATES OF MAJOR GRADING ACTIVITIES AND DETERMINE SEQUENCES OF TEMPORARY AND PERMANENT SOIL DISTURBING ACTIVITIES ON ALL PORTIONS OF THE PROJECT.
 - THE CONTRACTOR WILL BE REQUIRED TO MODIFY THE PLAN OR MATERIALS TO ADAPT TO SEASONAL VARIATIONS, CONSTRUCTION ACTIVITY VARIATIONS, OR AS DIRECTED BY THE ENGINEER.
 - APPLICABLE EROSION AND SEDIMENT CONTROL DEVICES AND IMPLEMENTATION PROCEDURES ARE SUPPLIED IN THE FDOT STANDARD INDEXES 104 AND 105 AND THE STATE OF FLORIDA EROSION AND SEDIMENT CONTROL DESIGNER AND REVIEW MANUAL (E&SC MANUAL).
 - THE ENGINEER IS RESPONSIBLE FOR DETERMINING IF ANY MODIFICATIONS OR ADDITIONAL CONTROLS ARE REQUIRED AND TO OBTAIN DEPLOYMENT SCHEDULES FOR THE IMPLEMENTATION OF ALL ADDITIONAL EROSION AND SEDIMENT CONTROL DEVICES FROM THE CONTRACTOR.
- (3) GENERAL NOTES:
 - (a) ALL EROSION AND SEDIMENT CONTROL DEVICES FOR EACH PHASE OF WORK ARE TO BE INSTALLED PRIOR TO BEGINNING WORK ON THAT PHASE.
 - INSTALL EROSION AND SEDIMENT CONTROL DEVICES WHERE LISTED IN THE CONTRACTOR'S APPROVED EROSION AND SEDIMENT CONTROL PLAN FOR PERIMETER CONTROLS BEFORE THE LAND IS DISTURBED.
 - PROVIDE SEDIMENT BARRIERS WHERE LISTED IN THE CONTRACTOR'S APPROVED EROSION AND SEDIMENT CONTROL PLAN FOR DITCH/SWALE CHECK DAMS DURING CONSTRUCTION.
 - PROVIDE INLET PROTECTION SYSTEMS AT INLET OPENINGS. (d)
 - COVER OR STABILIZE DISTURBED AREAS AS SOON AS POSSIBLE (e)
 - DO NOT DISTURB AN AREA UNTIL IT IS NECESSARY FOR CONSTRUCTION TO PROCEED.
 - TIME CONSTRUCTION ACTIVITIES TO LIMIT IMPACT FROM SEASONAL CLIMATE CHANGES OR WEATHER EVENTS
 - DO NOT REMOVE PERIMETER CONTROLS UNTIL ALL UPSTREAM AREAS ARE FULLY STABILIZED AND PERMANENT VEGETATION IS ESTABLISHED.
- (4) AREA ESTIMATES:

TOTAL BASIN AREA:

48.36 ACRES (FROM ORIGINAL DRAINAGE MAPS).

TOTAL AREA TO BE DISTURBED:

0.03 ACRES

RUNOFF COEFFICIENTS BEFORE CW (B), DURING CW (D) AND AFTER CW (A) CONSTRUCTION:

RUNOFF COEFFICIENT FOR: GRASSED AREAS: C=0.20 IMPERVIOUS ROADWAYS AND PAVED SHOULDER: C=0.95 DISTURBED AREAS, EXPOSED SOIL, ETC., DURING CONSTRUCTION: VARIES C=0.40 TO 0.60

WEIGHTED RUN-OFF COEFFICIENT:

BEFORE: Cw(B) = 0.70DURING: Cw(D) = 0.50

THE RUN-OFF COEFFICIENT DURING CONSTRUCTION, Cw (D), IS CALCULATED ASSUMING THAT THE MAXIMUM ALLOWABLE AREA OF SOIL IS DISTURBED DURING CONSTRUCTION.

DESCRIPTION OF SOIL OR QUALITY OF DISCHARGE.

THE SOILS ARE MODERATELY WELL DRAINED, WITH VERY LOW RUNOFF CLASSIFICATION AND HAVE LOW WATER TABLE DEPTH. THESE SOILS HAVE MODERATELY LOW TO HIGH CAPACITY TO TRANSMIT WATER (0.06 TO 1.98 IN/HR). THE ROADWAY SOIL SURVEY WAS NOT CONTAINED IN THE CONSTRUCTION PLANS.

DEPTH TO SHWE HYDROLOGIC GROUP

24 - MILLHOPPER-URBAN FINE SAND (0 TO 5% SLOPES) (53%-40%) 48 - TAVARES-URBAN FINE SAND (5 TO 12% SLOPES) (50%-40%)

REFERENCE: USDA SOIL SURVEY OF ORANGE COUNTY FLORIDA

- (7) ESTIMATED DRAINAGE FLOW DIRECTION AND AVERAGE SLOPE OF DRAINAGE AREA FOR EACH OUTFALL: (a) SITE MAP:
- RECEIVING WATERS:

THE PROJECT IS CONTAINED WITHIN THE HOWELL CREEK BASIN AS DEFINED BY SJRWMD (OPEN BASIN) AND IT IS NOT CONSIDERED AS AN OUTSTANDING FLORIDA WATER (OFW).

(9) THE OUTFALLS ARE 303(d) LISTED, IMPAIRED WATERS FOR PARAMETERS SUCH AS N/A

(a) N/A

(10) OUTFALL LOCATIONS: (TEMPORARY AND PERMANENT)

DESCRIPTION *LATITUDE* LONGITUDE SPRING LAKE (3080101) N 28° 33' 16" W 81° 24' 04'

- (11) SURFACE WATER IMPACTS ARE ANTICIPATED WITHIN THE PROJECT LIMITS.
- (12) DESCRIPTION OF STORMWATER MANAGEMENT: (EXISTING/PROPOSED)
 - EXISTING DRAINAGE FLOWS ARE TYPICALLY CONVEYED THROUGH STORM SEWER INLETS & PIPES,
 - OFF-SITE RUNOFF SHOULD BE DIVERTED AWAY OR THROUGH THE CONSTRUCTION AREA, IF POSSIBLE. THIS ADDITIONAL FLOW, IF NOT DIVERTED, CAN ADD VOLUME AND SIZE TO STRUCTURAL PRACTICES, REQUIRING MORE FREQUENT MAINTENANCE AND LIMITING EFFECTIVENESS OF EROSION AND SEDIMENT
 - THE CONTRACTOR WILL PROVIDE POLLUTION CONTROL BY IMPLEMENTING DUST CONTROL DURING ALL PHASES OF CONSTRUCTION. SEDIMENT CONTROL WILL BE ACCOMPLISHED BY USING STREET OR VACUUM
 - THE CONTRACTOR SHALL TAKE ALL REASONABLE PRECAUTIONS TO PREVENT UNAUTHORIZED MATERIALS FROM ENTERING WETLANDS, WATERWAYS, OTHER SURFACE WATERS OR WATERS OF THE U.S.
- II. CONTROLS.

SEDIMENT AND EROSION CONTROLS

- (1) WATER QUALITY MONITORING:
 - (a) WATER QUALITY MONITORING SHALL BE CONDUCTED IN ACCORDANCE WITH THE SPECIAL CONDITIONS OF ANY ENVIRONMENTAL PERMIT OR BY THE CONTRACTOR UPON THE OBSERVATION THAT WATER QUALITY STANDARDS MAY BE VIOLATED BY THE CONTRACTOR'S ACTIVITIES. MONITORING LOCATIONS MAY BE SPECIFIED IN THE ENVIRONMENTAL PERMIT OR MAY BE DESIGNATED BY THE CONTRACTOR AND APPROVED BY THE PROJECT ADMINISTRATOR.
 - THE PROJECT ADMINISTRATOR WILL BE RESPONSIBLE FOR MONITORING ANY ACTIVITIES FOR VIOLATION OF WATER QUALITY STANDARDS AS THEY RELATE TO TURBIDITY (NO GREATER THAN 29 NEPHELOMETRIC TURBIDITY UNITS (NTU) ABOVE BACKGROUND OR GREATER THAN O NTU ABOVE BACKGROUND FOR DIRECT DISCHARGES TO OFW'S).
 - IF WATER QUALITY STANDARDS ARE VIOLATED, CONSTRUCTION SHALL BE STOPPED IMMEDIATELY, THE ENVIROMENTAL PERMIT CONDITIONS FOLLOWED AND EROSION AND SEDIMENT CONTROL DEVICES REEVALUATED AND APPROVED BY THE PROJECT ADMINISTRATOR PRIOR TO ANY CONTINUATION OF ACTIVITY. MONITORING ACTIVITIES AND TURBIDITY READINGS SHALL BE RECORDED ON THE CONSTRUCTION INSPECTION REPORT AND CONTINUED UNTIL TURBIDITY READINGS FALL BELOW AN ACCEPTABLE LEVEL (LESS THAN 29 NTU'S ABOVE BACKGROUND OR LESS THAN 0 NTU'S ABOVE BACKGROUND FOR DIRECT DISCHARGES TO OFW'S).
 - WATER QUALITY MONITORING MAY BE CONDUCTED DURING ANY PHASE OF CONSTRUCTION AS DIRECTED BY THE PROJECT ADMINISTRATOR.

REVISIONS HNTB CORPORATION DATE DESCRIPTION DATE DESCRIPTION BARRY J. SWITZER, P.E. FL REGISTRATION NO. 43422 610 CRESCENT EXECUTIVE CT SUITE 400 LAKE MARY, FL 32746 (407) 805-0355 CERT. OF AUTH. NO. 6500

STATE OF FLORIDA DEPARTMENT OF TRANSPORTATION ROAD NO. COUNTY FINANCIAL PROJECT ID ORANGE 431734-1-72-09

STORMWATER POLLUTION PREVENTION PLAN

SHEET NO.

- (a) STABILIZATION MEASURES SHALL INCLUDE, BUT NOT BE LIMITED TO MAINTAINING, ESTABLISHING AND USING VEGETATION, APPLYING MULCHES, SODDING, SEEDING, BEST MANAGEMENT PRACTICES (BMP) AND THE USE OF ROLLED EROSION CONTROLLED PRODUCTS. WHEN CONSTRUCTION ACTIVITIES HAVE TEMPORARILY OR PERMANENTLY CEASED, SIDE SLOPES SHALL BE STABILIZED WITH PERFORMANCE SODDING OR SEEDING OR ANY OTHER APPROVED METHOD OF STABILIZATION INCLUDED IN THE STATE OF FLORIDA EROSION AND SEDIMENT CONTROL DESIGNER AND REVIEW MANUAL (E&SC MANUAL).
- STABILIZATION SHALL TAKE PLACE AS SOON AS PRACTICAL IN PORTIONS OF THE PROJECT WHERE CONSTRUCTION ACTIVITIES HAVE CEASED, BUT NO LATER THAN 7 DAYS AFTER ANY CONSTRUCTION ACTIVITY CEASES EITHER TEMPORARILY OR PERMANENTLY.
- ALL EROSION CONTROL DEVICES SHALL BE INSTALLED ACCORDING TO THE CONTRACT DOCUMENTS, AND THE CONTRACTOR'S APPROVED EROSION CONTROL PLAN.
- ANY TEMPORARY MATERIAL USED FOR POLLUTION OR EROSION AND SEDIMENT CONTROL DURING CONSTRUCTION SHALL BE REMOVED AT THE COMPLETION OF THE PROJECT AND FINAL STABILIZATION OF THE PROJECT HAS BEEN ACHIEVED.
- (e) THE CONTRACTOR SHALL BE RESPONSIBLE FOR MODIFYING SOIL TRACKING PREVENTION SYSTEMS OR PROCEDURES AS NEEDED.
- (3) STRUCTURAL PRACTICES FOR EROSION AND SEDIMENT CONTROL
 - (a) ROLLED EROSION CONTROL PRODUCTS (ARTIFICIAL COVERINGS)

PURPOSE: TO PROTECT DISTURBED SLOPE SURFACES AGAINST EROSION DUE TO RAINFALL OR FLOWING WATER.

- (1) USED FOR PAUSES IN CONSTRUCTION DUE TO INCLEMENT WEATHER OR OTHER CIRCUMSTANCES. COULD INCLUDE NATURAL OR SYNTHETIC FIBER MATS, PLASTIC SHEETING OR NETS.
- (2) USED FOR EROSION CONTROL THAT FACILITATES PLANT GROWTH WHILE PERMANENT GRASS IS ESTABLISHED. COULD INCLUDE BIODEGRADABLE EROSION CONTROL BLANKETS INSTALLED ON A SEEDED AREA, ON FILL SLOPES OR IN DITCHES.
- (3) USED TO STABILIZE DRAINAGE CHANNELS. CONSULT E&SC MANUAL TO DETERMINE CORRECT PRODUCT TYPE FOR CHANNEL STABILIZATION.
- (b) RUNOFF CONTROL STRUCTURE (TEMPORARY SLOPE DRAIN)

PURPOSE: TO PROTECT HILLSIDE SURFACES AGAINST EROSION DUE TO CONCENTRATED FLOW OF RUNOFF WATER.

- (1) USED ON FILL SLOPES AND CUT SLOPES TO REDUCE SEDIMENT TRANSPORT AND COULD INCLUDE TEMPORARY SLOPE DRAINS, GRASS-LINED CHANNELS, ROCK-LINED CHANNELS AND CHECK DAMS.
- (2) RUNOFF CONTROL STRUCTURES TYPICALLY DISCHARGE TO A SEDIMENT BASIN.
- (c) SEDIMENT BASIN (CONTAINMENT SYSTEM)

PURPOSE: A CONTAINMENT SYSTEM IS DESIGNED TO DETAIN AN ADEQUATE VOLUME OF RUNOFF, REDUCE THE VELOCITY OF FLOW THROUGH THE SYSTEM. ALLOW FOR SETTLEMENT OF SUSPENDED SOLIDS AND REGULATE THE DISCHARGE RATE FROM THE SEDIMENT BASIN.

- (1) SEDIMENT BASINS MUST BE PLACED IN STRATEGIC LOCATIONS WITHIN THE ACTIVE AREAS OF CONSTRUCTION. CONTRIBUTING AREA AND SIZE OF TARGET SOIL PARTICLE WILL DICTATE WHETHER THE SEDIMENT BASIN WILL BE TYPE 1, TYPE 2 OR TYPE 3 SYSTEM.
- (2) THE USE OF SMALLER PRE-SEDIMENTATION BASINS USED IN CONJUNCTION WITH LARGER PERMANENT RETENTION/DETENTION PONDS ARE EFFECTIVE IN CAPTURING LARGER VOLUMES OF SEDIMENTS. THIS TECHNIQUE REQUIRES PERIODICALLY SCHEDULED REMOVAL OF THE ACCUMULATED SEDIMENTS.
- (d) SEDIMENT BARRIERS (TEMPORARY CONSTRUCTION SITE BEST MANAGEMENT PRACTICES (BMP))

PURPOSE: SEDIMENT BARRIERS EITHER OBSTRUCT FLOW OR PREVENT THE PASSAGE OF WATER WHILE CONSTRUCTION ACTIVITIES OCCUR. SMALLER SEDIMENT BARRIERS MAY FUNCTION AS A SMALL SEDIMENT CONTAINMENT SYSTEM OR AS A METHOD TO REDUCE FLOW VELOCITY.

- (1) THESE CONSTRUCTION BMP'S CAN INCLUDE SYNTHETIC BALES, STAKED SILT FENCE, TURBIDITY BARRIER, STORM SEWER INLET BARRIERS, ROCK BARRIERS, GEOSYNTHETIC BARRIERS, ETC.
- (2) APPROPRIATE LOCATIONS INCLUDE SITE PERIMETER, BELOW DISTURBED AREAS SUBJECT TO SHEET AND RILL EROSION, BELOW THE TOE OF EXPOSED AND ERODIBLE SLOPES, ALONG THE TOE OF STREAM AND CHANNEL BANKS, AROUND DRAINS AND INLETS LOCATED IN LOWPOINTS OR THE DOWNSTREAM EDGE OF AREAS UNDERGOING VERTICAL OR BOX CULVERT CONSTRUCTION ACTIVITIES.
- (3) INAPPROPRIATE LOCATIONS FOR THESE SAME MEASURES INCLUDE PARALLEL TO A HILLSIDE CONTOUR, IN CHANNELS WITH CONCENTRATED FLOW (UNLESS PROPERLY REINFORCED), UPSTREAM OR DOWNSTREAM OF CULVERTS WITH CONCENTRATED FLOW, IN FRONT OF OR AROUND INLETS ON A GRADE WITH CONCENTRATED FLOW OR IN FLOWING STREAMS.

(e) FLOATING TURBIDITY BARRIER

PURPOSE: USED IN PERMANENT BODIES OF WATER TO RETAIN SEDIMENT AND FLOATING DEBRIS FROM A CONSTRUCTION AREA SO THAT REMOVAL OR CONTAINMENT OF THE MATERIAL IS POSSIBLE. THEY ARE ALSO USED TO CONTROL MIGRATION OF SUSPENDED SEDIMENTS.

- (1) TYPE I, LIGHT DUTY, IS USED WHERE THERE IS LITTLE OR NO CURRENT, NO WIND AND NO WAVE ACTION.
- (2) TYPE II, MODERATE DUTY, IS USED WITH SOME CURRENT (<3.5 FT. PER SECOND) AND SOME EXPOSURE TO WIND.
- TYPE III, HEAVY DUTY, IS USED WITH GREATER CURRENT (3.5-5.0 FT. PER SECOND), MODERATE WIND AND WAVE ACTION
- (4) BARRIER MUST BE ATTACHED AT BOTH ENDS AND WEIGHTED ON THE BOTTOM.
- MULTIPLE LINES OF BARRIER MAY BE USED IN SOME CIRCUMSTANCES FOR ADDITIONAL PROTECTION.
- STANDARD PANELS FOR WATER DEPTHS ARE 5.0'. ADDITIONAL PANELS CAN BE USED FOR WATER DEPTHS > 5.0'.

(f) STAKED TURBIDITY BARRIER

PURPOSE: THIS ITEM IS COMMONLY USED IN AREAS WHERE CONTINUOUS CONSTRUCTION ACTIVITIES CHANGE THE NATURAL CONTOURS AND DRAINAGE RUNOFF PATTERNS.

- (1) COMMONLY USED IN LAKES AND STREAMS AS A SEDIMENT CONTAINMENT SYSTEM. SHOULD NOT BE USED WHERE WATER CURRENTS MOVE THE CURTAIN AND DISLODGE COLLECTED SEDIMENTS.
- MAXIMUM DEPTH OF PANEL IS 3'-8".
- POST MUST BE A MINIMUM LENGTH OF 5.0' AND A MINIMUM OF 10" OF FABRIC MUST BE IMBEDDED IN THE GROUND.

(g) INLET PROTECTION SYSTEM

PURPOSE: ANY OF A NUMBER OF SEDIMENT BARRIERS THAT EITHER PREVENT SEDIMENT FROM ENTERING AN INLET OR TRAP THE SEDIMENTS ONCE THEY ENTER THE INLET.

- (1) TYPICAL APPLICATIONS INCLUDE ROCK BARRIERS, FRAME AND FILTER BARRIERS, CURB INLET "SUMP" BARRIER, CURB INLET DIVERSION BERM, CURB AND GUTTER SEDIMENT CONTAINMENT SYSTEM OR CURB
- (2) SHOULD BE INSTALLED ONLY WHEN CONSTRUCTION ACTIVITIES ARE ON-GOING AND ONLY WHERE SUMP CONDITIONS EXIST.
- SHOULD NOT BE USED WHEN CONSTRUCTION IS COMPLETE AND SHOULD NOT BE USED IN AREAS WHERE FLOODING COULD ENCROACH INTO THE TRAVEL LANES.

(h) SOIL TRACKING PREVENTION DEVICE

PURPOSE: TEMPORARY STRUCTURES TO ASSIST WITH THE REMOVAL OF SOIL MATERIAL CAPTURED ON VEHICLE TIRES BEFORE THE VEHICLES ENTER THE ROADWAY.

- (1) USE ONE DEVICE PER MILE WITH A MINIMUM OF TWO PER PROJECT.
- USE ADDITIONAL DEVICES FOR CONSRUCTION AREAS THAT ARE NOT ADJACENT TO THE ROAD RIGHT OF WAY AND NO ACCESS IS PROVIDED THROUGH A SOIL TRACKING PREVENTION DEVICE.
- RRR PROJECTS SHOULD BE HANDLED ON A CASE BY CASE BASIS.

REVISIONS HNTB CORPORATION DESCRIPTION DESCRIPTION BARRY J. SWITZER, P.E. FL REGISTRATION NO. 43422 610 CRESCENT EXECUTIVE CT SUITE 400 LAKE MARY, FL 32746 (407) 805-0355 CERT. OF AUTH. NO. 6500

STATE OF FLORIDA DEPARTMENT OF TRANSPORTATION ROAD NO. COUNTY FINANCIAL PROJECT ID SR 50 ORANGE 431734-1-72-09

STORMWATER POLLUTION PREVENTION PLAN

SHEET NO.

PURPOSE: REDUCE SOIL EROSION THROUGH SOIL BINDING, USED AS A WATER TREATMENT ADDITIVE TO REMOVE SUSPENDED SOLIDS FROM RUNOFF, PROVIDES APPROPRIATE MEDIUM FOR GROWTH OF VEGETATION FOR STABILIZATION AND INCREASES INFILTRATION BY INCREASING SIZE OF SOIL PARTICLE.

- (1) CAN BE USED ON DISTURBED SOILS. CAN BE USED IN CONJUNCTION WITH OTHER BMP'S TO ENHANCE PERFORMANCE. CAN BE APPLIED IN DISSOLVED FORM WITH WATER, CAN BE USED AS A DRY POWDER, CAN BE USED IN GRANULAR FORM OR MAY BE USED IN THE FORM OF FLOC LOGS.
- (2) HIGHER CONCENTRATIONS OF PAM'S DON'T INCREASE THE EFFECTIVENESS OF THE PRODUCT.
- (3) ACTIVELY WORKED AREAS WILL REQUIRE REAPPLICATION TO REMAIN EFFECTIVE.
- PAM SHOULD NOT BE USED WHERE THE IS A POTENTIAL FOR EQUIPMENT CLOGGING OR TOXICITY IS A CONCERN.
- (b) CHEMICAL TREATMENT ALUM

PURPOSE: REMOVE SUSPENDED SOLIDS AND POLLUTANTS BY ENMESHMENT AND ABSORPTION INTO ALUM. COLLECT FLOCS OF SUSPENDED SEDIMENTS IN RUNOFF AND STORE THEM IN SEDIMENT BASINS OR STORMWATER MANAGEMENT FACILITIES.

- (1) ALUM IS INJECTED INTO THE FLOW STREAM CONTAINING TURBID WATER. INJECTION IS CONTROLLED BY VARIABLE SPEED CHEMICAL PUMP TO FEED ALUM AT MULTIPLE TREATMENT POINTS. ALUM TREATMENT IS EFFECTIVE IN TREATMENT OF RUNOFF THAT CONTAINS LIMEROCK FROM UNPAVED SURFACES.
- (2) ALUM TREATMENT REQUIRES CLOSE MONITORING OF DOSAGE. COMBINATION WITH OTHER COMPOUNDS MAY VIOLATE TOXICITY REQUIREMENTS AND THE USE OF ALUM MAY LOWER Ph LEVELS.

THIS PAY ITEM IS CONSIDERED A CONTRACTOR'S OPTION FOR SEDIMENT CONTROL ISSUES THAT ARE PROJECT/SITE SPECIFIC. NOT TO BE USED IN THE DESIGN PROCESS WITHOUT CONTACTING LARRY RITCHIE IN THE STATE CONSTRUCTION OFFICE.

(5) DEWATERING OPERATIONS (OPTIONAL - BASED ON PROJECT APPLICABILITY)

DESCRIPTION: DEWATERING OPERATIONS ARE PRACTICES THAT MANAGE THE DISCHARGE OF TURBID WATER WHEN WATERS OTHER THAN STORMWATER AND ACCUMULATED SURFACE WATERS MUST BE REMOVED FROM A LOCATION SO THAT CONSTRUCTION WORK MAY BE ACCOMPLISHED. THESE WATERS CAN INCLUDE GROUNDWATER, WATER FROM COFFERDAMS, WATER DIVERSIONS AND WATERS USED DURING CONSTRUCTION THAT MUST BE REMOVED FROM A WORK AREA.

- (a) ENVIRONMENTAL AGENCIES ARE ESPECIALLY CONCERNED WITH THE PROTECTION OF WETLANDS FROM DRAWDOWN EFFECTS, PROTECTING RECEIVING BODIES FROM SEDIMENTATION AND POSSIBLE CAPACITY LIMITATIONS.
- THREE PRIMARY METHODS OF DEWATERING COMMONLY USED IN FLORIDA ARE RIM-DITCHING, SOCK/PIPE/HORIZONTAL WELLS AND WELL-POINT SYSTEMS.
- METHODS FOR CONTAINING SEDIMENTATION CAN INCLUDE A COMBINATION OF BMP'S AND SEDIMENT TRAPS, SEDIMENT BASINS, GRAVITY BAG FILTERS, WEIR TANKS, DEWATERING TANKS, SAND MEDIA/PRESSURIZED BAGS AND CHEMICAL TREATMENTS.
- (6) COASTAL OPERATIONS (OPTIONAL BASED UPON PROJECT LOCATION):

DESCRIPTION: CONSTRUCTION SITES IN COASTAL AREAS PRESENT UNIQUE CHALLENGES DUE TO HIGHER WIND SPEEDS, SALINE LADEN AIR MOISTURE AND WAVE ACTION THAT REQUIRE USING APPROPRIATE EROSION CONTROL TECHNIQUES THAT CAN WITHSTAND THESE ELEMENTS.

- PARTICULAR CONCERNS DURING THE DEVELOPMENT OF EROSION CONTROL PLANS IN COASTAL OPERATIONS CAN INCLUDE THE RESISTANCE OF EROSION CONTROL MATERIALS TO SALT WATER, HIGH WATER TABLES, SOIL COMPACTION AND SITE DEVELOPMENT DUE TO THE TYPICAL SANDY SOILS LOCATED IN THESE AREAS AND SOIL STABILIZING VEGETATION MUST BE SALT TOLERANT.
- HIGH ENERGY ENVIRONMENT SHOULD BE CONSIDERED WHEN SELECTING EROSION CONTROL DEVICES. FREQUENT MAINTENANCE IS NORMALLY REQUIRED FOR EROSION CONTROL DEVICES AND TIDAL FLUCTUATIONS MUST BE CONSIDERED WHEN SELECTING THE METHODS OF EROSION CONTROL.
- (c) TEMPORARY CONTROL TECHNOLOGIES FOR THE COASTAL ENVIRONMENT COULD INCLUDE THE USE OF COMPOST/WOOD MULCHING, HYDRAULIC MULCHING, SOIL BINDERS AND TEMPORARY HYDROSEEDING.
- PERMANENT CONTROLS COULD INCLUDE THE USE OF POLYMER-ENHANCED ARMORING, PRESERVING EXISTING VEGETATION WHEN POSSIBLE, ESTABLISHING PERMANENT SALT-TOLERANT VEGETATION, CONSTRUCTION SITE BARRIERS (SHEET PILES/CONCRETE WALLS/EARTHERN BERMS), NATURAL /SYNTHETIC GEOTEXTILES, MATS, OR GEOGRIDS.

III. OTHER CONTROLS:

- (1) WASTE DISPOSAL
 - (a) THE CONTRACTOR WILL PROVIDE LITTER CONTROL AND COLLECTION WITHIN THE PROJECT BOUNDARIES DURING CONSTRUCTION ACTIVITIES.
 - ALL FERTILIZER AND CHEMICAL CONTAINERS SHALL BE DISPOSED OF BY THE CONTRACTOR ACCORDING TO EPA'S STANDARD PRACTICES AS DETAILED BY THE MANUFACTURER.
 - (c) NO SOLID MATERIALS, INCLUDING BUILDING AND CONSTRUCTION MATERIALS, SHALL BE DISCHARGED TO WETLANDS OR BURIED ON SITE.
 - ALL SANITARY WASTE WILL BE COLLECTED FROM PORTABLE UNITS BY A LICENSED SANITARY WASTE MANAGEMENT CONTRACTOR AS REQUIRED BY STATE REGULATIONS.
- (2) OFF-SITE VEHICLE TRACKING WILL BE CONTROLLED BY THE FOLLOWING METHODS:
 - (a) LOADED HAUL TRUCKS ARE TO BE COVERED BY A TARPAULIN AT ALL TIMES.
 - EXCESS DIRT ON ROAD WILL BE REMOVED DAILY.
- (3) STATE AND FEDERAL REGULATIONS: PERMITS WILL BE REQUIRED FROM THE FOLLOWING AGENCIES:

NONE

(4) NON-STORMWATER (INCLUDING SPILL REPORTING) THE CONTRACTOR WILL PROVIDE THE FDOT WITH AN EROSION AND SEDIMENT CONTROL PLAN THAT WILL INCLUDE SPILL CONTAINMENT, REPORTING, AND RESPONSES. THE PLAN SHALL SPECIFY WHAT MANAGEMENT PRACTICES AND CONTAINMENT METHODS WILL BE USED TO PREVENT POTENTIAL POLLUTANTS (FUEL, LUBRICANTS, HERBICIDES, ETC.) FROM SPILLING ONTO THE SOIL OR INTO THE SURFACE WATERS. IF A SPILL DOES OCCUR, OR IF CONTAMINATED SOIL OR GROUNDWATER IS ENCOUNTERED, CONTACT THE FDOT DISTRICT 5 HAZARDOUS WASTE COORDINATOR AT (386) 943-5000.

IV. MAINTENANCE:

THE CONTRACTOR SHALL BE RESPONSIBLE FOR MAINTENANCE AND REPAIRS OF ALL EROSION AND SEDIMENT CONTROL DEVICES AND REMOVAL OF EROSION AND SEDIMENT CONTROL DEVICES WHEN NOTICE OF TERMINATION IS MAILED. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE REMOVAL AND PROPER DISPOSAL OF SEDIMENT BUILDUP THROUGH THE LIFE OF THE INSTALLED EROSION AND SEDIMENT CONTROL DEVICES.

- (1) ALL CONTROL MEASURES WILL BE MAINTAINED DAILY BY THE CONTRACTOR AND ALL MEASURES WILL BE MAINTAINED IN GOOD WORKING ORDER. IF A REPAIR IS NECESSARY, IT WILL BE INITIATED IMMEDIATELY.
- (2) SODDING WILL BE INSPECTED FOR BARE SPOTS, WASHOUTS, AND HEALTHY GROWTH.
- SYNTHETIC BALES SHALL BE MAINTAINED TO ENSURE THEIR USEFULNESS AND NOT BLOCK OR IMPEDE STORMWATER FLOW OR DRAINAGE.
- STABILIZED CONSTRUCTION ENTRANCES SHALL BE MAINTAINED TO PREVENT CLOGGING OF ROCK BEDDING WHICH MAY IMPEDE THE USEFULNESS OF THE STRUCTURE.

V. INSPECTION:

- (1) THE CONTRACTOR SHALL INSTALL AND MAINTAIN RAIN GAUGES ON THE PROJECT SITE AND RECORD WEEKLY RAINFALL IN ACCORDANCE WITH THE NPDES PERMIT.
- (2) ALL EROSION AND SEDIMENT CONTROL MEASURES WILL BE INSPECTED DAILY BY CONTRACTOR'S PERSONNEL WHO ARE F.D.E.P. CERTIFIED STORMWATER MANAGEMENT INSPECTORS. ALL EROSION CONTROL DEVICES WILL BE INSPECTED WITHIN 24 HOURS OF A RAINFALL EVENT OF 0.5 INCHES OR GREATER.
- (3) THE CONTRACTOR SHALL COMPLETE ALL SWPPP INSPECTION REPORT FORMS REQUIRED FOR THE NPDES PERMIT.

VI. TRACKING AND REPORTING:

- (1) THE CONTRACTOR SHALL SUBMIT A WEEKLY REPORT TO THE DEPARTMENT DOCUMENTING THE DAILY INSPECTIONS AND MAINTENANCE OR REPAIRS TO THE EROSION AND SEDIMENT CONTROL DEVICES. THE CONTRACTOR SHALL MAINTAIN ALL REQUIRED REPORTS AND COMPLETE ALL SWPPP INSPECTION FORMS.
- (2) PREPARATION OF ALL THE CONTRACTOR'S REPORTS OF INSPECTION, MAINTENANCE AND REPAIRS REQUIRED FOR THE CONTROL AND ABATEMENT OF EROSION AND WATER POLLUTION, SHALL BE INCLUDED IN THE INDIVIDUAL COSTS OF THE EROSION AND SEDIMENT CONTROL DEVICES OR LUMP SUM COST OF THE PROJECT.
- (3) THE CONTRACTOR SHALL USE THE SWPPP CONSTRUCTION INSPECTION REPORT FORM # 650-040-03, FOR DAILY INSPECTIONS.

REVISIONS HNTB CORPORATION DATE DESCRIPTION DATE DESCRIPTION BARRY J. SWITZER, P.E. FL REGISTRATION NO. 43422 LAKE MARY, FL 32746 (407) 805-0355 CERT. OF AUTH. NO. 6500

610 CRESCENT EXECUTIVE CT SUITE 400

STATE OF FLORIDA DEPARTMENT OF TRANSPORTATION ROAD NO. COUNTY FINANCIAL PROJECT ID SR 50 ORANGE 431734-1-72-09

STORMWATER POLLUTION PREVENTION PLAN

SHEET NO.

