

CHROME ELECTRIC, LLC.

500 S. PARK AVE. TITUSVILLE, FL 32796
PH (321) 267-0990 FAX (321) 267-3253

PROPOSAL:

Remove and Replace Type 145 Exterior Wall Mount fixtures

TO: City of Orlando
ATTN: Ian Lahiff

DESCRIPTION: Install New Type 145 fixtures.

1. Provide all material and labor to perform the following.
2. Remove 132ea existing Type 145 light fixtures and replace. The intent of this scope is that Chrome Electric will support and hand over the new light fixtures, mounting hardware, and caulk for complete removal and installation by Rhino Staging.
 - a. The details below are an example of the effort required but may vary slightly.
3. Provide all equipment, rigging, tools, and labor to perform the following:
 - a. Remove and replace 132ea Type 145 fixtures.
 - b. Remove old fixture and transport to Event Level Marshalling area.
 - i. Scrape old caulking from existing plate.
 - c. Install new fixtures.

Connect existing flex to back of new fixture and insert duct seal in end of flex to control condition air.

- i. Terminate wiring and close cover.
 - ii. Caulk around new back box with 100% silicone caulk to new plate.
 - iii. Remove all trash and clean up areas worked.
- d. Recycle lamps and ballasts
- e. Dispose of demoed light fixtures.
- f. A 60ft boom lift will be required to access 20ea fixtures on the South West corner of the building.

Exclusions:

1. Due to the excessive cost of accessing the fixture that requires hiring a rigging crew, Chrome electric will not be providing a labor warranty for the Type 145 light fixtures.
2. Per discussions 3ea spare type 145 fixtures will be provided instead of the 5% spare parts requirement.
3. The Type 145 light fixtures that are behind the Amway signs will not be changed since there is not enough room to access them.
 - a. The existing circuit wiring will still run through these fixtures and is not to be altered.
4. No trouble shooting or re-working of existing lighting conduit or circuit wiring is included in this proposal.

5. Pricing provided is for the Arcadia AEW9991 fixture. If it is determined that this fixture does not get approved, then revised pricing will be submitted for a different fixture.
6. If the City feel best that an 3/16" weep hole in ballast box is best to allow for condensation drainage, Chrome will drill a drain hole; this may void the manufactures warranty.

Price includes payroll tax, insurance and required documentation.

TOTAL PROPOSAL: \$ 291,136.65

Chrome Electric, LLC.

Date: 5/10/18

CHROME ELECTRIC, LLC.

500 S. PARK AVE. TITUSVILLE, FL 32796
PH (321) 267-0990 FAX (321) 267-3253

PROPOSAL: **Space Heaters @ Amway**

TO: City of Orlando
ATTN: Ian Lahiff

DESCRIPTION: Provide and Install 20 Space Heater

1. Provide all material and labor per plans.

Install 20ea SALPHAH3-60240 Heaters
2ea 45kva Transformers
3ea Electrical Panels
20 Contactors and 3 enclosures
Lutron Field Services to connect to Amway Lighting system.
All conduit and wire.
Painted conduit outside.

Exclusions:

No field services are include for adding panel into existing gear. If field services are required an change order would be required.

Price includes payroll tax, insurance and required documentation.

TOTAL PROPOSAL: \$ 88,771.27

William Butcher
Chrome Electric, LLC.

Date: 5/8/18